





Annotated List of Properties

Westfield Town North-WA

Photo	Address/Date/ Condition/Alterations	Description	Rating: S,C,NC
	<p>7551 Bliss St.</p> <p>Date: ca. 1830 Condition: Excellent Alterations: Rear addition, Windows</p> <p>MAP FRAME: B4</p>	<p>1½ -story, side-gabled, Greek Revival house with center-ridge chimney, 5-bays wide, eyebrow windows, center door with sidelights, entablature, and pilasters. Sheathed with wood shingles.</p>	C
	<p>7040 Bliss St.</p> <p>Date: ca. 1840 Condition: Good Alterations: asbestos siding</p> <p>MAP FRAME: B5</p>	<p>1½ -story, front-gabled, Greek Revival farmhouse with side wing, asbestos siding, 2/2 windows. The property is notable for its farm outbuildings.</p>	C
	<p>7040A Bliss St. Barn 1:</p> <p>Date: ca. 1930 Condition: Good Alterations:</p> <p>MAP FRAME: B5</p>	<p>2½ -story, side-gambrel, roof barn with an enclosed gambrel entry on the barn side. The barn has multiple windows and an entry door on end. It has two silos.</p>	S
	<p>7040B Bliss St. Barn 2:</p> <p>Date: ca. 1890 Condition: Good Alterations:</p> <p>MAP FRAME: B5</p>	<p>1-story, 3-bay, side-gabled, barn with rear shed addition, vertical board siding, 2 wagon doors and 2 metal cribs.</p>	S





Annotated List of Properties

Westfield Town North-WA

Photo	Address/Date/ Condition/Alterations	Description	Rating: S,C,NC
	<p>7551A Bliss St. Barn 1:</p> <p>Date: ca. 1900 Condition: Good Alterations: Possible rear addition</p> <p>MAP FRAME: B4</p>	<p>1½ -story, T-shaped, barn with side-gabled main block and a long, rectangular gabled addition, vertical board siding. The main block has an entry in the gable end.</p>	<p>C</p>
	<p>7551B Bliss St. Barn 2:</p> <p>Date: c. 1890 Condition: Good Alterations: Built in 2 sections</p> <p>MAP FRAME: B4</p>	<p>1½-story, 3-bay, bank barn with sliding wagon doors on the barn side. It has a slightly lower side-gabled section on the south.</p>	<p>C</p>
	<p>7616 Bliss St.</p> <p>Date: 1840s Condition: Excellent Alterations: Highly altered – new clapboard, windows, dormers</p> <p>MAP FRAME: B4</p>	<p>1½ -story, side-gabled, Greek Revival house, 5-by 2-bays, center entrance with entablature and pilasters, dentil cornice, 3 gable dormers on front slope, rear addition with wall dormers and integral porch. Barn on property in excellent condition with medium integrity.</p>	<p>NC</p>
	<p>7160 Hardenburg Rd.</p> <p>Date: ca. 850s Condition: Good Alterations: House highly altered-vinyl siding, windows.</p> <p>MAP FRAME: A4</p>	<p>This property is notable for its late 19th century barn, which is a 2-story, L-shaped side-gabled block and a front facing gable containing an entry bay. Vertical board siding. Barn is in good condition with medium integrity.</p>	<p>House-NC Barn- C</p>

Annotated List of Properties

Westfield Town North-WA

Photo	Address/Date/ Condition/Alterations	Description	Rating: S,C,NC
	<p>7488 Hardenburg Rd.</p> <p>Date: ca. 1915 Condition: Good Alterations: Windows</p> <p>MAP FRAME: A4</p>	<p>2½ -story, front-gabled, Colonial Revival house entirely made of rock-faced concrete block, round porch is partly recessed 2 diamond-shaped windows.</p>	<p>C</p>
	<p>6704A Light Road Barn 1, east side:</p> <p>Date: ca. 1880 Condition: Fair Alterations: Associated house completely altered with no integrity</p> <p>MAP FRAME: B4</p>	<p>1½ -story, front-gabled, bank barn with entry on lower story of barn side. Siding is vertical board.</p>	<p>C</p>
	<p>6704B Light Road Barn 2, west side:</p> <p>Date: ca, 1880 Condition: Good Alterations: Garage door on barn. Associated house completely altered with no integrity.</p> <p>MAP FRAME: B4</p>	<p>1½ -story, front-gabled, barn with shed roof extension, roof supports tree trunks, the garage door and hay door are in the gable end. Siding is vertical board.</p>	<p>C</p>
	<p>7080 Munson Rd.</p> <p>Date: ca. 1920 Condition: Excellent Alterations: Vinyl siding, windows</p> <p>MAP FRAME: B4</p>	<p>2-story, Dutch Colonial Revival with side gambrel roof and shed dormer. This property is notable for its barn- see below.</p>	<p>NC</p>





Annotated List of Properties

Westfield Town North-WA

Photo	Address/Date/ Condition/Alterations	Description	Rating: S,C,NC
	<p>7080A Munson Rd.</p> <p>Date: ca. 1900 Condition: Excellent</p> <p>Alterations: Siding replaced, doors replaced, shed roof porch</p> <p>MAP FRAME: B4</p>	<p>Though this barn has been substantially refurbished, the fieldstone foundation indicates its age. 1½ - story, 3-bay, side-gabled barn, 2 wagon doors on barn side, board and batten siding, 2/2 windows</p>	C
	<p>7853 NY Route 5</p> <p>Date: early –mid 19th c. Condition: Excellent Alterations: Chimneys, windows, side addition.</p> <p>MAP FRAME: A4</p>	<p>2-story, side-gabled, brick, 5-by 2 – bay, Federal/Greek house. Transom above door, stone sills.</p>	C
	<p>Lakeside B&B 8223 NY Route 5 (Barcelona)</p> <p>Date: early –mid 19th c. Condition: Excellent Alterations: Entry porch, side porch, windows, rear addition, dormer.</p> <p>MAP FRAME: A4</p>	<p>2-story, side-gabled, brick, 5- by 2- bay, Federal/Greek house. Elliptical fanlight above door, sidelights. Exterior end chimneys.</p>	C
	<p>8284 NY Route 5</p> <p>Date: ca. 1920 Condition: Excellent</p> <p>MAP FRAME: A4</p>	<p>1½ -story, side-gabled, Craftsman bungalow with enclosed porch contained under the roof. Brick and wood shingle exterior.</p>	C


Annotated List of Properties

Westfield Town North-WA

Photo	Address/Date/ Condition/Alterations	Description	Rating: S,C,NC
	<p>8604 NY Route 5</p> <p>Date: early –mid 19th c. Condition: Good</p> <p>Previously inventoried – No determination</p> <p>MAP FRAME: A4</p>	<p>2-story, side-gabled, brick, 5-by 2- bay, Federal/Greek house.</p>	C
	<p>14 Prospect St.</p> <p>Date: 1868 Condition: Excellent</p> <p>MAP FRAME: A4</p>	<p>1½- story, front-gabled, Italianate house with a hipped-roof side wing. Decorative details include door enframement, paired, round-arched windows with shutters, brackets.</p>	S
	<p>14 Prospect St.</p> <p>Barns 1 & 2</p> <p>Date: ca. 1900 Condition: Excellent Alterations:</p> <p>MAP FRAME: A4</p>	<p>1) 1 ½ story, side-gabled, barn with vertical board siding and silo</p> <p>2) 1 ½ story, front-gabled dairy barn with multiple windows, and silo.</p>	S
	<p>14 Prospect St. Barns 3 & 4</p> <p>Date: ca. 1900 Condition: Excellent Alterations:</p> <p>MAP FRAME: A4</p>	<p>3) 1½- story, front-gabled, barn with enclosed entry bay in the gable end. It has a milk shed and silo</p> <p>4) 1-story, front-gabled, barn.</p>	S




Annotated List of Properties

Westfield Town North-WA

Photo	Address/Date/ Condition/Alterations	Description	Rating: S,C,NC
	<p>7362 Prospect St.</p> <p>Date: ca. 1900 Condition: Good Alterations: 1 story rear addition</p> <p>MAP FRAME: A5</p>	<p>1½ -story, side-gabled, vernacular house with novelty wood siding, 6/6 windows, concrete foundation.</p>	<p>C</p>
	<p>7371 Prospect St.</p> <p>Date: ca. 1850 Condition: Good Integrity: Low Alterations: House- vinyl siding and replaced windows</p> <p>MAP FRAME: A5</p>	<p>A highly modified Greek Revival farmhouse. This property is notable for its ca. 1900 barn, which has a wide, side-facing gambrel roof. It is in good condition with high integrity.</p>	<p>House- NC Barn- C</p>
	<p>7428 US Route 20</p> <p>Date: ca. 1830 Condition: Excellent Alterations: Porch, windows, chimneys</p> <p>MAP FRAME: A5</p>	<p>2-story, brick , side-gabled, 5- by 2- bay, Federal house.</p>	<p>C</p>
	<p>7540 US Route 20</p> <p>Date: ca. 1850 Condition: Excellent Alterations: Windows, additions, porch</p> <p>MAP FRAME: A4</p>	<p>1½ -story, front-gabled, Greek Revival house, wood shingles.</p>	<p>C</p>





Annotated List of Properties

Westfield Town North-WA

Photo	Address/Date/ Condition/Alterations	Description	Rating: S,C,NC
	<p>7548 US Route 20</p> <p>Date: ca. 1850 Condition: Excellent Alterations:</p> <p>MAP FRAME: A4</p> <p>Previously inventoried – No Determination</p>	<p>1½ - story, brick, side-gabled, Gothic Revival house with decorative vergeboards and paired, pointed-arched windows.</p>	<p>S</p>
	<p>8248 US Route 20</p> <p>Date: ca. 1840 Condition: Excellent Alterations: Windows</p> <p>MAP FRAME: B4</p>	<p>1½ -story, side-gabled, Greek Revival house with rear wing addition, 6/6 windows. This property is notable for its barn- see below.</p>	<p>C</p>
	<p>8248A US Route 20</p> <p>Date: ca. 1890 Condition: Good Alterations: Shed addition, doors.</p> <p>MAP FRAME: B4</p>	<p>1½- story, front-gabled, barn with shed addition, entry in gable end, siding is clapboard.</p>	<p>C</p>
	<p>Westfield No 5 School 8243 US Route 20</p> <p>Date: ca. 1852 Condition: Excellent Alterations: Converted into residence. Shed-roof addition. MAP</p> <p>MAP FRAME: B4</p>	<p>1-story, front-gabled, frame, vernacular one room school with wood shingle.</p>	<p>C</p>





Annotated List of Properties

Westfield Town North-WA

Photo	Address/Date/ Condition/Alterations	Description	Rating: S,C,NC
	<p>8361 US Route 2 Date: ca. 1920 Condition: Excellent Alterations: front steps</p> <p>MAP FRAME: B4</p>	<p>1-story, hipped-roof, Craftsman Bungalow with wood shingle, enclosed porch, rock-faced concrete block foundation</p>	C
	<p>8406 US Route 20</p> <p>Date: ca. 1850 Condition: Good Alterations: Substantially altered, original details uncertain (Greek Revival)</p> <p>MAP FRAME: B4</p>	<p>This property is notable for its late 19th century barn. It has a 1½ - story, side-gabled, block with a secondary cross gable on the barn side with sliding wagon doors and hay door. Siding is clapboard and vertical board, There is a silo adjacent.</p>	House- NC Barn-C
	<p>8418 US Route 20</p> <p>Date: ca. 1920s Condition: Excellent Alterations: windows</p> <p>MAP FRAME: B4</p>	<p>1½ -story, hipped-roof Craftsman bungalow with multiple dormers, siding is wood shingle.</p>	S
	<p>Margaret Peacock House/ Johnson Winery 8419 US Route 20</p> <p>Date: 1820s Condition: Excellent Alterations: Renovations (1906, 1914, 1961) Rear addition, side addition, windows</p> <p>MAP FRAME: B4</p>	<p>2½ -story, side-gabled, Federal/Greek transitional house, 3- by 3- bays, brick, corbelled cornice and belt course, transom and sidelights, stone lintel over door, brick jack arches over windows, pressed metal roof, 2 end chimneys on west side. The 1½ -story side wing is a modern addition based on a historic atlas engraving.</p>	S


Annotated List of Properties

Westfield Town North-WA

Photo	Address/Date/ Condition/Alterations	Description	Rating: S,C,NC
	<p>Johnson Winery Barn 8419A US Route 20</p> <p>Date: 1900 Condition: Excellent Alterations: Shed wing</p> <p>MAP FRAME: B4</p>	<p>1-story, barn with sliding wagon doors on gable end, shed addition, vertical plank.</p>	<p>S</p>
	<p>Westfield (T); barn complex; south side of US Route 20, approx. 750 ft west of Jillson Road</p> <p>Date: c. 1900 Condition: Fair to good</p> <p>MAP FRAME: B4</p>	<p>Dairy barn complex 1) 1½- story, gambrel-roof dairy barn with ventilators ca. 1910; 2) round roof dairy barn ca. 1945; 3) 2 concrete silos recent (ca. mid-20th century)</p>	<p>C</p>
	<p>8567 US Route 20</p> <p>Date: ca.1840 Condition: Good Alterations: Asbestos shingle, rear addition, side porch either added or repaired</p> <p>MAP FRAME: B4</p>	<p>1½ -story, front gable with wing Greek Revival farmhouse with asbestos shingle, 6/6 windows, entry door in west bay with heavy entablature, pilasters and ¾ sidelights.</p>	<p>C</p>
	<p>8608 US Route 20</p> <p>Date: ca.1920 Style: Colonial Revival Condition: Good Alterations: Windows</p> <p>MAP FRAME: B4</p>	<p>2-story, hipped-roof, American Foursquare with clay tile roof, brick, concrete foundation, full-width front porch with brick piers.</p>	<p>C</p>

Annotated List of Properties

Westfield Town North-WA

Photo	Address/Date/ Condition/Alterations	Description	Rating: S,C,NC
	<p>8608A US Route 20</p> <p>Date: ca.1900 Condition: Fair to Good Alterations: Missing/boarded windows</p> <p>MAP FRAME: B4</p>	<p>1½ -story, 3-bay, side-gabled, carriage house, clapboard, front wall dormer over entrance on barn side, rear wing.</p>	<p>C</p>
	<p>8641 US Route 20</p> <p>Date: ca.1880 Condition: Good Alterations: Vinyl siding, windows</p> <p>MAP FRAME: B4</p>	<p>2½- story, front-gabled, Vernacular house with a rock faced concrete block foundation. This property is notable for its barn, which is T-shaped with a front gable and side wing, board and batten siding. It is in good condition with medium integrity.</p>	<p>House- NC Barn-C</p>
	<p>8750 US Route 20</p> <p>Date: ca. 1860 Condition: Excellent Alterations: Windows</p> <p>MAP FRAME: B4</p>	<p>2½ -story, L-shaped, Italianate house with front gable and side wing, center ridge chimney, clapboard, brackets, porch with turned posts.</p>	<p>S</p>
	<p>8750A US Route 20</p> <p>Date: ca. 1900 Condition: Good</p> <p>MAP FRAME: B4</p>	<p>Long, side-gabled, barn with 2 entry bays on the barn side, clapboard siding.</p>	<p>C</p>

Annotated List of Properties

Westfield Town North-WA

Photo	Address/Date/ Condition/Alterations	Description	Rating: S,C,NC
	<p>8783 US Route 20</p> <p>Date: ca. 1885 Condition: Excellent Alterations:</p> <p>MAP FRAME: B4</p>	<p>1½- story, side-gabled, Queen Anne farmhouse with 2 front facing gables, turret over porch, clapboard, Queen Anne windows.</p>	<p>S</p>
	<p>8783A US Route 20</p> <p>Date: ca. 1890 Condition: Good Alterations: Garage door, windows</p> <p>MAP FRAME: B4</p>	<p>1½- story, 3-bay, side-gabled, barn with door on barn side, clapboard siding.</p>	<p>C</p>
	<p>8820 US Route 20</p> <p>Date: ca.1880 Condition: Good Integrity: Medium Alterations: Windows, asphalt shingles</p> <p>MAP FRAME: B3</p>	<p>2-½ story, front-gabled, vernacular farmhouse, with wall dormer. Property is notable for its barn- see below</p>	<p>C</p>
	<p>Dist. No. 4 School 8850 US Route 20</p> <p>Date: 1878 Condition: Good Alterations: Converted into a residence. Entrance porch, windows, west side addition</p> <p>MAP FRAME: B3</p>	<p>1-story, front-gabled, vernacular, one room schoolhouse, segmental-arched windows, corner piers, 3-by 3-bays on original block, with 1 bay rear addition, roof brackets Panel says "Dist No 4 West Ripley AD 1878"</p>	<p>S</p>

Annotated List of Properties

Westfield Town North-WA

Photo	Address/Date/ Condition/Alterations	Description	Rating: S,C,NC
	<p>8820A US Route 20</p> <p>Date: ca. 1900 Condition: Good</p> <p>MAP FRAME: B3</p>	<p>2-bay garage/barn with sliding doors, vertical plank siding, "Chew" sign painted on east side above door, surrounded by grape vines.</p>	S
	<p>Oliver Stetson Tavern 8922 US Route 20</p> <p>Date: ca. 1815 Condition: Poor/Vacant</p> <p>*Slated for demolition by owner (Personal communication: Michelle Henry, Chaut. Cty. Historian)</p> <p>MAP FRAME: B3</p>	<p>2-story, side-gabled, Federal tavern with paired end chimneys, segmental-arched porch, corbelled cornice, splayed lintels, 1-story east wing also has segmental arch entrance porch, side gable and center ridge chimney. Oliver Stetson Tavern, 1818 (Ripley Sesquicentennial, p. 7)</p>	S
	<p>7041 Walker Road</p> <p>Date: ca. 1835 Condition: Excellent Alterations: Windows, north wing</p> <p>MAP FRAME: B4</p>	<p>2½ -story, L-shaped Greek Revival with front facing main block and wing, clapboard.</p>	S
	<p>7041A Walker Road</p> <p>Date: ca. 1900 Condition: Excellent Alterations: Novelty siding</p> <p>MAP FRAME: B4</p>	<p>2-story, bank barn with sliding wagon doors and hay door on the gable end, mixed-fieldstone foundation, clapboard siding and exposed rafter tail ends.</p>	S